FORM MR-MO (Revised 7/87)

July 11, 1988

FOR DIVISION US	E ONLY	
File #:	M /	1
Date Received:	· 7	1
Date Approved:	1	1
DOGM Lead:		

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING
355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203
Telephone: (801) 538-5340

NOTICE OF INTENTION TO COMMENCE MINING OPERATIONS
MINING AND RECLAMATION PLAN

Based on Provisions of the Mined Land Reclamation Act, Title 40-8, Utah Code Annotated 1953, General Rules and Regulations and Rules of Practice and Procedures, By Order of the Board of Oil, Gas- and Mining.

This form applies only to mining operations which disturb or will disturb greater than five acres at any given time.

"MINING OPERATIONS" means those activities conducted on the surface of the land for the exploration for, development of, or extraction of a mineral deposit, including, but not limited to, surface mining and the surface effects of underground and in situ mining, on-site transportation, concentrating, milling, evaporation, and other primary processing.

"Mining operation" does not include: the extraction of sand, gravel, and rock aggregate; the extraction of oil and gas as defined in Chapter 6, Title 40; the extraction of geothermal steam; smelting or refining operations; off-site operations and transportation; or reconnaissance activities which will not cause significant surface resource disturbance or involve the use of mechanized earth-moving equipment such as bulldozers or backhoes.

PLEASE NOTE:

If extra space is required to complete a section, please attach additional steets and include cross-referenced page numbers as necessary. The operator may submit this information on an alternate form, however the same or similar format must be used.

I. GENE	RAL INFORMATION (Rule R613-005-104)
1.	Mine Name: A TO IBEX, KEYSTONE & MONARCH
2.	Mineral(s) to be Mined: GOLD, SILVED
3.	Name of Applicant or Company: Jumbo MINING COMPANY Corporation (X) Fartnership () Individual ()
4.	Permanent Address: 6305 FERN SPRING COUE  AUSTIN, TX  78730
5.	Company Representative (or designated operator):  Name: E.B. KING  Title: PRESIDENT  Address: 6305 FERN SPRING OUE AUSTIN, TX  Phone: 512-346-4537
6.	Location of Operation:  County(ies) JUAB + MILLARD COUNTIES  Township: 143 Range: 11W Section: 35+36  Township: 155 Range: 10 Section: 6,7+8  Township: 155 Range: 11W Section: 1
7.	Ownership of the and surface: Private (Fee), Public Domain (BLM), National Forest (LSFS), State of Utah or other:
PRIVATE- STATE LEASE BLM BLM BLM 8.	Name:  Name:  Name:  Address:  Address:  Address:  Address:  Address:  Address:
	Name: <u>FBEX</u> GOLD Address: As ABOUE  Name: <u>Jumbo MINING</u> (o Address: AS ABOUE  Name: <u>Asoma (Imam)</u> , <u>Tuc</u> Address: As AROVE  Name: Address:
9.	Have the above owners been notified in writing? Yes $\times$ No If no, why not?
10.	Does the operator have legal right to enter and conduct mining operations on the land covered by this notice? Yes X No.

### II. MAPS (Rule R613-005-105)

#### 1. Base Map

A true and correct topographic base map (or maps) with appropriate contour intervals must be submitted with this Notice which show all of the items on the following checklist. The scale should be approximately 1 inch = 2,000 feet (preferably a USGS 7.5 minute series or equivalent topographic map where available) showing the location of lands to be affected in sufficient detail to permit calculation of proposed surface disturbance.

#### Map Checklist

Please check off each section as it is drawn on the map(s). Does the map show:

- (a) Property boundaries of surface ownership of all lands which are to be affected by the mining operations;
- (b) Perennial streams, springs and other bodies of water, roads, buildings, landing strips, electrical transmission lines, water wells, oil and gas pipelines, existing wells or boreholes, or other existing surface or subsurface facilities within 500 feet of the proposed mining operations; (None)
- (c) Proposed route of access to the mining operations from nearest publicity maintained highway (Map scale appropriate to show access);
- (d) Known areas which have been previously impacted by mining or exploration activities within the proposed mining permit area.
- (e) Acreages proposed to be disturbed or reclaimed each year (or other suitable time period SEE ALSO EXHIBIT A

## 2. Surface Facilities Map

A surface facilities map shall be provided at a scale of not less than 1" = 500'.

		EXABIT A LITTLE
TOUS 02E	TONS	ACRES VEGETATION BE TO BE DISTURBED SURVEY REVELETATED STABILIZED
ALTP 90,000	-80,000	PIT = 1.00 VEG. = 30% WASTE DUMP PIT +
7		WASTE 2.66 BARB 10%
IBEX 10,000 GROUP	1,000 (E# ANY)	DELLUE = 27 ROCK = 95% WASTE DUMP TOP 125 AC.
KEYSTONE TEST 5,000		Rack = 85%  VED = 40%  BARE = 15%  CRAWO 15%
MONARK TEST 15,000	9	ROCK = 75%  34 VE 6 2 10% 0 .34 A=
NEW HAULAGE		1.79 VEG = 40% 4.79 AU 0
HAULAGE ROAD		ROLK = 25% OAC
ON EXIST-		BARE 259 BUM + County CROUDS AS ROADS
PIT 88,000	135,000	THE MIZPAH BIT IS TO FLED AS AN AMENDMENT AFTER THE SOIL AND UEGETATION SURVEYS HAVE BEEN TAKE
NORTHRING PIT 184, 500	410,000	THERE WILL BE NO NEW ACREAGE DISTURBED AT THE DRUM MINE AND
MINE  CUDERTROAD  - 50. PIT		DISTURBED AT THE DRUM MUE AND RECLAMATION WILL BE IN ACCORDANCE 1 WITH RERMIT # ACT/027/007
DRUM 9,000		
TOTAL 411,000	626,000	1. 194 ROCK = 408690 C. 93 Ac 2.76 4C

## Map Checklist

Please check off each section as it is drawn on the map. Does the map show:

- (a) Proposed surface ficilities, including but not limited to buildings, stationary mining/processing equipment, roads, utilities, power lines, proposed drainage control structures, and the location of topsoil storage areas, overburden/waste dumps, tailings or processed waste facilities, disposal areas for overburden, solid and liquid wastes, and wastewater discharge, treatment and containment facilities; See WSMC ALSO
- (b) A border clearly outlining the extent of the surface disturbed area proposed to be affected by mining, and the number of acres proposed to be affected; SEE EXHIBIT A
- (c) The location of known test borings, pits, or core holes.
- 3. Additional Maps

Additional maps and drawings may be required as applicable in accordance with Rule R613-005-105.3.

# III. OPERATION PLAN (Rule R;13-005-106)

Acreage to be disturbed:


Minesite (operating, storage, disposal areas, etc.):	4.90 Ac
Access/naul roads/conveyors:	6.29 AL
Associated on-site processing facilities:	0
PROCESSING AREA WILL BE AT THE Total:	11.19

2. Describe methods and procedures to be employed for mining, on-site processing and concurrent reclamation.

900 10 mm	DEE EXHIBIT	5

3. Depth to groundwater (if known) NOT KNOWN

≥800 ft.



11	
	7/87)
	- 5 -
	Thickness of soil material to be stockpiled.  Area from which soil material can be salvaged  Volume of soil to be stockpiled  (cross reference with item IV-17)
	Thickness of overburden ft.
	Thickness of mineral deposit.
	Volume of refuse, tailings, and processing waste stockpiles. 491,000 Tons OR 307,000 cu. yds.
	Acreage of tailings ponds and water storage ponds to be constructed.  WILL USE DRUM MINE PONDS  NA acres
	Describe how topsoil or subsoil material will be removed, stockpiled and protected.  NA
	Described to the second
	Describe how overburden material will be removed and stockpiled.  NA
	Describe how tailings, waste rock, rejected materials, etc. will be disposed of. ASTE ROCK WILL BE DRILLED, BLASTED AND MOVED TO PERMANENT DUMP SITES (SEE MAPS). ROCK WILL BE MOVED 34 8-10 4D RUBBER TIRE LOADERS, DG CAT AND.  35 TON HAW PACKS. Potentially toxic materials must be analyzed for toxicity. Describe
	Describe how tailings, waste rock, rejected materials, etc. will be disposed of. LASTE ROCK WILL BE DRILLED, BLASTED AND MOVED TO PERMANENT DUMP SITES (SEE MAPS). ROCK WILL BE MOVED 34 8-10 4D RUBBER TIRE LOADERS, D9 CAT AND.  35 TON HAM PACKS

13. For each tailings pond, sediment pond, or other major drainage control structures, attach design drawings and typical

cross-sections. NA

FOOTNOTE

THE PROPOSED PIT, TEST PITS AND UNDERGROUND DECLINE ALL LIE ON RUCKY RIDGETOPS AND STEEP HILLSIDES AND HAVE VERY LITTLE OR NO SOIL DEVELOPMENT, ALL AREAS HAVE HAD PREVIOUS SURFACE MINING OZ EXPLORATION DISTURBANCE. SEE PHOTOS FOR VEGETATION, SOIL AND LAND DISTURBANCE. SINCE SOIL DEVELOPMENT IN THE PIT AND WASTE DUMP AREA IS NEGLICIBLE, THERE WILL BE NO REMOVING AND STOCKPILING OF SOIL.

vege		ired to return the land to a useful t 70 percent of the premining red on site before mining or on mined).
~	ground cover percentage figur aging the vegetation type(s) chment I for sampling methods	e is determined by sampling and on the areas to be mined (see ).
(a)	Vegetation Survey The follow completed based upon the veg	ing information needs to be etation survey:
	Sampling method used Scul	
	Number of plots or transects	.65
	Ground Cover	Percent
	Vegetation (perennial grass, forb and shrub cover)	34.60 SEE EXH
	Litter	AND PHO
	Rock/rock fragments	40.86
	Bare ground	24.54 100%
	Revegetation Requirement - 70 of above vegetation figure)	24.22 %

- (b) Photographs The operator may submit photographs (prints) of the site sufficient to show existing vegetation conditions. These photographs should show the general appearance and condition of the area to be affected and may be utilized for comparison upon reclamation of the site. Photographs should be clearly marked as to the location, orientation and the date that the pictures were taken.
- 16. Soils The plan shall include an order 3 Soil Survey (or similar) and map. This information is needed to determine which soils are suitable for stockpiling for revegetation. This soil data may be available from the local Soil Conservation Service office, or if on public lands, from the land management agency. The map needs to be of such scale that soil types can be accurately determined on the ground (see attachment I).
  - (a) Each soil type to be disturbed needs to be field analyzed for the following: SEE FOOTNOTE FOR ITEM III 4

Depth of soil material Volume (for stockpiling) Texture (field determination)	<u> </u>	inches cu.yds.
pH (field determination) (cross reference with item	IV - 5)	= :

(b) Where there are problem soil areas (as determined from the field examination) laboratory analysis may be necessary for some or all of the following parameters:

Electrical Conductivity	
Sodium Adsorption Ratio	
Saturation %	
Organic matter percentage	
Available F	
Available N-NO3	
pH (laboratory)	
Texture (1:boratory)	

NOTE: Soil samples to be sent to the laboratory for analysis need to be about one pint in size, properly labeled, and in plastic bags. Each of the soil horizons on some sites may need to be sampled.

17. Provide a narrative description of the geology of the area and/or a geologic cross section. THE DRUM MTNS CONSIST OF A WESTERMY DILATED FAULT BCOCK COMPOSED OF 10,000 FEET OF PRECAMBRIAN AND CAMBRIAN AND CAMBRIAN AND SHALE, THESE ROCKS HAVE BEEN INTRUDED BY QUARTE DIORITE, QUARTE MONZON ON THE OUTER FRINGES.


NOLCANIC ROCKS OVERLIE THE LIMESTONES


MINERALIZATION OCCUPANTION ROCKS OVERLIE THE LIMESTONES

MINERALIZATION OCCURS ALONG HIGH ANGLE NORMAL FAULTS AND FAUDRABLE LIMESTONE BEDS. SILICA, IRON AND GOLD HAVE REPLACED THE LIMESTONE ALONG CERTAIN FRUITS AND BEDS.

IV.	IMPACT ASSESSMENT	CRule	R613-005-108)	

	12	lease provide a general narrative description identifying potential process and/or subsurface impacts. Where applicable, this description would include surface and groundwater systems, species of high interest their critical habitats, existing soil resources for reclamation, ope stability, ercsion control, air quality, and public health and sety.  SEE EXHIBIT
٧.	 DF	CLAMATION BLAN 45
••		CLAMATION PLAN (Rule R613-005-109)  List current land use(s) other than mining:
	2.	List future post-reclamation land-use(s) proposed: GRAZING
	3.	Describe each phase of reclamation of the minesite in detail under the following categories:
		(a) Disposal of Trash  Describe how building, foundations, trash and other waste materials  will be disposed of. THERE SHOULD BE NO FOUNDATIONS, TRASH  AND OTHER WASTE MATERIALS AT THE PITS - DISPOSAL  AT MILLSITE (DRUM MINE) WILL BE IN ACCORDANCE WITH THE  (b) Backfilling and Grading  Describe equipment and methods to be employed, amount of materials to be moved and final disposition of any stockpiled materials.
		(c) <u>Soil Material Replacement</u> In order to reestablish the required ground cover, one to two feet (depending on underlying material) of suitable soil material usually has to be redistributed on the areas to be reseeded. If the stockpiled soil isn't sufficient for this, soil borrow areas will need to be located.
		How much soil material is planned to be put on the area to be reseeded? inches





Where will this material come from?  ———————————————————————————————————
How will it be transported and spread?  NA
(d) Seed Bed Preparation  Describe how the seedbed will be prepared and equipment to be used. WASTE DUMP TOPS AND NEW HALLAGE ROADS  WILL RIPPED
(The Division recommends ripping or discing six inches deep)  (e) Seed Mixture - List the species to be seeded:
Specie; Name  Specie; Name  (1bs Pure Live Seed/Acre)  WESTERN L'HEATERASS  20 LBS / ACRE
INDIAN RICEGRASS  NEEDLE + THREAD GRASS  FOUR - WING SALEBRUSH
(The Division recommends seeding 20 lbs./acre of native and introduced adaptable species of grass, forb, and browse seed and will provide a specific species list if requested)
(f) Seeding Method  Describe method of planting the seed. DRILLING AND OR  HAND BROADCAST IN EARLY FALL
(The Division ecommends planting the seed with a rangeland or farm drill, or if broadcast seeded, harrow or rake the seed 1/4 to 1/2 inch into the soil. Fall is the preferred time to seed)
(g) Fertilization  Describe ferti ization method and rate. Show D NOT BE NEEDED  WITH THIS TYPE OF VEGETATION BUT VISUAL EXAMINATION  6-12 MONTHS FFTER SEEDING WILL DETERMINE IF FERTILIZERS ARE NEED  (The Division recommends broadcast fertilization at the time of seeding of 200 lbs./acre of diammonium phosphate 18-46-0)
(h) Other Revigetation Procedures  If other reclamation procedures, such as mulching, irrigation, etc., are planned, describe them. MULCHING AND IRRIGATION SHOULD  NOT BE NEEDED BUT VISUAL EXAMINATION AFTER SEEDING  WILL DETERMINE IF OTHER PROCEDURES.

### VI. VARIANCE (Rule R613-005-111):

Any planned deviations from rule R613-005-007 (Operating Practices) or Rule R613-005-010 (Reclamation Practices) must be identified below.

Rule Number	Title/Category
<del></del>	<del></del>

For each variance requested, attach a narrative statement describing and delineating the area proposed to be affected by the variance, justifying the need for the variance, and discussing alternate methods or measures to be utilized.

## VII. SURETY (Rule R613-005-112)

A Reclamation surety must be provided to the Division prior to final approval of this application. In calculating this amount, the Division will consider the following major steps:

- 1) Clean-up and removal of structures.
- 2) Backfilling, grading and contouring.
- 3) Soil material redistribution and stabilization.
- 4) Revegetation (preparation, seeding, mulching)
- 5) Safety and fencing.
- 6) Monitoring.

To assist the Division in determining a reasonable surety amount, please attach a reclamation cost estimate which addresses each of the above steps.

#### VIII. SIGNATURE REQUIREMENT

I hereby certify that the f	oregaing()   Arue and correct.
Signature of Operator:	- E Minar
Name (typed or print):	E.B. KING
Title of Operator:	PRESIDENT
Date:	7/11/88
DE NOTE.	

#### PLEASE NOTE:

Section 40-8-13(2) of the Mined Land Reclamation Act provides for maintenance of confidentiality concerning certain portions of this report. Please check to see that any information desired to be held confidential is so abeled and included on separate sheets or maps. Only information relating to the <u>location</u>, size or nature of the deposit may be protected as confidential.

Confidential Information Enclosed: () Yes () No

## Attachment I

## Vegetation Cover Sampling

Vegetation cover sampling determines the amount of ground that is covered by live vegetation. It is divided into four categories which equal 100 percent. They are:

<u>Vegetation</u> - This is the live perennial vegetation. Care should be taken to avoid sampling in disturbed areas that have a large percentage of annual or weedy vegetation, such as cheatgrass and russian thistle.

<u>Litter</u> - This is the dead vegetation on the ground, such as leaf and stem litter.

Rock/rock fragments - This is the rock and rock fragments on the soil surface.

Bare ground - This is the bare soil which is exposed to wind and water erosion.

# Cover Sampling - The following methods are acceptable:

#### Ocular Estimation

This method visually estimates the percentage of ground covered in a plot by the four components. Plot size is usually a meter or yard square or a circular plot 36 inches in diameter. Ten to 20 plots should be randomly sampled in each major vegetation type.

## Line Intercept

Percent ground cover is obtained by stretching a tape measure (usually 100') over the ground and then recording which of the four components is under each foot mark. At least two of these transects should be randomly laid out and measured in each major vegetation type.

## Soil Survey and Sampling Methods

If a SCS or land management agency soil survey is not available, the operator shall delineate all soil types that will be disturbed by mining on a map. Each soil type shall be sampled for its characteristics and inherent properties. Representative sampling locations should have similar geologic parent material, slopes, vegetative communities and aspects. The sampling locations should be representative of the soil type and be identified on the map. Sampling shall be at a minimum of one (1) for each soil type disturbed.

The soil map needs to be of sufficient scale so that each soil type can be accurately located on the ground.